



NOTE:

- CONCRETE SLAB MUST BE FINISHED WITH RUBBER SOFTFALL
- EXTERNAL EVENT: 800 CASCADE ROPE NET, 800 CABLE ROPE NET CLIMBER, 1200 CASCADE ROPE NET AND 2000 SCALING WALL TO BE MOUNTED TO CONCRETE SLAB
- EXTERNAL EVENTS: 1200 SLIDE & GLIDE RAILS AND 2000 STRAIGHT TUBE SLIDE, TO BE INSTALLED WITH IN-GROUND FOOTINGS
- EXTERNAL EVENT: 4400 SPIRAL TUBE SLIDE HAS ONE SUPPORT LEG SURFACE MOUNTED AND ONE IN-GROUND FOOTING
- IF EXTERNAL EVENT/S CHANGE FROM THIS DESIGN, A REVIEW AND ALLOWANCE MUST BE ALLOWED FOR, TO REDESIGN CONCRETE SLAB SIZE, FOOTING AMOUNTS AND LOCATIONS, AND MINIMUM FALLZONE REQUIREMENTS

Site Layout is indicative only & subject to change.
This design is confidential & subject to Copyright.

SCALE BAR 1:60@A3
0 1 5 m

Design Plan

Design No: **T0018(OC)-C**

Drawn by: **J.H.**

Date drawn: **19/10/2022**